

Design Guide Advanced Harmonic Filters







### Contents

1 How to Read this Design Guide	3
2 Safety and Conformity	4
2.1.2 Abbreviations	4
2.1.3 CE Conformity and Labelling	4
2.1.4 EMC-Directive 2004/108/EG	5
2.1.5 Warnings	5
3 Introduction to Harmonics and Mitigation	7
3.1 What are Harmonics?	7
3.1.1 Linear Loads	7
3.1.2 Non-linear Loads	7
3.1.3 The Effect of Harmonics in a Power Distribution System	9
3.2 Harmonic Limitation Standards and Requirements	9
3.3 Harmonic Mitigation	11
4 Introduction to Advanced Harmonic Filters	12
4.1 Operation Principle	12
4.1.1 Power Factor	13
4.1.2 Capacitor Disconnect	14
5 Selection of Advanced Harmonic Filter	15
5.1 How to Select the Correct AHF	15
5.1.1 Calculation of the Correct Filter Size Needed	15
5.1.2 Calculation Example	15
5.1.3 Voltage Boost	15
5.2 Electrical Data	16
5.2.1 Accessories	26
5.3 General Specification	27
5.3.1 General Technical Data	27
5.3.2 Environmental Data	27
6 How to Install	29
6.1 Mechanical Mounting	29
6.1.1 Safety Requirements of Mechanical Installation	29
6.1.2 Mounting	29
6.1.3 Recommendations for Installation in Industrial Enclosures	29
6.1.4 Ventilation	29
6.2 Electrical Installation	32
6.2.1 Over Temperature Protection	32
6.2.2 Capacitor Disconnect	32



#### Contents AHF005/010 Design Guide

6.2.3 Wiring	34
6.2.4 Fuses	35
6.3 Mechanical Dimensions	36
6.3.1 Sketches	36
6.3.2 IP00 Enclosures	46
6.3.3 Physical Dimension	53
6.3.4 IP00 Dimensions	53
6.3.5 Weight	54
7 How to Programme the Frequency Converter	55
7.1.1 DC-link Compensation Disabling	55
Index	56





# 1 How to Read this Design Guide

This Design Guide will introduce all aspects of the Advanced Harmonic Filters for your VLT® FC Series Drive. It describes Harmonics and how to mitigate them, provide installation instructions and guidance about how to programme the frequency converter.

Danfoss technical literature is also available online at www.danfoss.com/BusinessAreas/DrivesSolutions/Documentations/Technical+Documentation.

# 2

## 2 Safety and Conformity

#### 2.1.1 Symbols

Symbols used in this manual

#### NOTE

Indicates something to be noted by the reader.



Indicates a general warning.

# **AWARNING**

Indicates a high-voltage warning.

★ Indicates default setting

#### 2.1.2 Abbreviations


Active Power	P
Advanced Harmonic Filter	AHF
Alternating current	AC
American wire gauge	AWG
Ampere/AMP	A
Apparent Power	S
Degrees Celsius	°C
Direct current	DC
Displacement Power Factor	DPF
Electro Magnetic Compatibility	EMC
Drive	FC
Gram	g
Harmonic Calculation Software	HCS
Hertz	Hz
Kilohertz	kHz
Local Control Panel	LCP
Meter	m
Millihenry Inductance	mH
Milliampere	mA
Millisecond	ms
Minute	min
Motion Control Tool	MCT
Nanofarad	nF
Newton Meters	Nm
Nominal motor current	I <sub>M,N</sub>
Nominal motor frequency	$f_{M,N}$
Nominal motor power	P <sub>M,N</sub>
Nominal motor voltage	U <sub>M,N</sub>
Parameter	par.
Partial Weighted Harmonic Distortion	PWHD

Point of Common Coupling	PCC
Power Factor	PF
Protective Extra Low Voltage	PELV
Rated Inverter Output Current	l <sub>INV</sub>
Reactive Power	Q
Revolutions Per Minute	RPM
Second	sec.
Short circuit ratio	R <sub>SCE</sub>
Total Demand Distortion	TDD
Total Harmonic Distortion	THD
Total Harmonic Current Distortion	THiD
Total Harmonic Voltage Distortion	THvD
True Power Factor	TPF
Volts	V
I <sub>VLT,MAX</sub>	The maximum output current.
I <sub>VLT,N</sub>	The rated output current
	supplied by the frequency
	converter.



Equipment containing electrical components may not be disposed of together with domestic waste.

It must be separately collected with electrical and electronic waste according to local and currently valid legislation.



#### 2.1.3 CE Conformity and Labelling

#### What is CE Conformity and Labelling?

The purpose of CE labelling is to avoid technical trade obstacles within EFTA and the EU. The EU has introduced the CE label as a simple way of showing whether a product complies with the relevant EU directives. The CE label says nothing about the specifications or quality of the product.

#### The low-voltage directive (73/23/EEC)

Frequency converters must be CE labelled in accordance with the low-voltage directive of January 1, 1997. The directive applies to all electrical equipment and appliances used in the 50 - 1000V AC and the 75 - 1500V DC voltage ranges. Danfoss CE-labels in accordance with the directive and issues a declaration of conformity upon request.



#### 2.1.4 EMC-Directive 2004/108/EG

The Danfoss frequency converters comply with the requirements of the EMC -Directive. The AHF are inherently benign equipment, that means that they do not produce electromagnetic disturbances, consisting only of passive components. Therefore, AHF are not within the scope of the EMC-directive. Though, the Danfoss frequency converters in combination with AHF will observe the requirements of the EMC-Directive.

#### 2.1.5 Warnings

# **A**WARNING

Improper installation of the filter or the frequency converter may cause equipment failure, serious injury or death. Follow this Design Guide and install according to National and Local Electrical Codes.

# **AWARNING**

Never work on a filter in operation. Touching the electrical parts may be fatal - even after the equipment has been disconnected from the drive or motor.

# **AWARNING**

Before disconnecting the filter, wait at least the voltage discharge time stated in the Design Guide for the corresponding frequency converter to avoid electrical shock hazard.

# **ACAUTION**

When in use the filter surface temperature rises. DO NOT touch filter during operation.

# **ACAUTION**

To prevent resonances in the DC-link, it is recommended to disable the dynamic DC-link compensation by setting 14-51 DC Link Compensation to OFF. See chapter 7 How to Programme the Frequency Converter.

## **A**CAUTION

Temperature contactor must be used to prevent damage of the filter chokes caused by over temperature. An immediate stop or a controlled ramp down within 30 sec. has to be performed to prevent damage of the filter chokes.

#### NOTE

Never attempt to repair a defect filter.

#### NOTE

The filters represented in this Design Guide are specially designed and tested for operation with Danfoss frequency converters (FC 102/202/301 and 302). Danfoss takes no responsibility for the use of the filters with third party frequency converters.

## **AWARNING**

Non - authorized removal of required cover, inappropriate use, incorrect installation or operation, creates the risk of severe injury to persons or damage to material assets.

## **A**CAUTION

All operations concerning transport, installation and commissioning as well as maintenance must be carried out by qualified, skilled personnel (IEC 60364 and CENELEC HD 384 or IEC 60364 and IEC-Report 664 or DIN VDE 0110. National regulations for the prevention of accidents must be observed).

#### NOTE

According to this basic safety information qualified skilled personnel are persons who are familiar with the assembly, commissioning and operation of the product and who have the qualifications necessary for their occupation.

#### NOTE

The filters are components, that are designed for installation in electrical systems or machinery.

When installing in machines, commissioning of the filters (i.e. the starting of operation as directed) is prohibited until it is proven, that the machine corresponds to the regulations of the EC Directive 83/392/EEC (Machinery Directive); EN 60204 must be observed.

#### **NOTE**

Commissioning (i.e. starting operation as directed) is only allowed when there is compliance with the EMC-Directive 89/336/EEC.

The filters meet the requirements of the Low-Voltage Directive 73/23/EEC. The technical data and information on the connection conditions must be obtained from the nameplate and the documentation and must be observed in all cases.

#### **NOTE**

The filter must be protected from inappropriate loads. In particular; during transport and handling: Components are not allowed to be bent. Distance between isolation must not be altered. Touching of electronic components and contacts must be avoided.



#### **NOTE**

When measuring on live filters, the valid national regulations for the prevention of accidents (e.g. VBG 4) must be observed.

The electrical installation must be carried out according to the appropriate regulations (e.g. cable cross-sections, fuses, PE-connection). When using the filters with frequency converters without safe separation from the supply line (to VDE 0100) all control wiring has to be included in further protective measures (e.g. double insulated or shielded, grounded and insulated).

#### **NOTE**

Systems where filters are installed, if applicable, have to be equipped with additional monitoring and protective devices according to the valid safety regulations e.g. law on technical tools, regulations for the prevention of accidents, etc.



## 3 Introduction to Harmonics and Mitigation

#### 3.1 What are Harmonics?


#### 3.1.1 Linear Loads

On a sinusoidal AC supply a purely resistive loads (for example an incandescent light bulb) will draw a sinusoidal current, in phase with the supply voltage.

The power dissipated by the load is:

 $P = U \times I$ 

For reactive loads (such as an induction motor) the current will no longer be in phase with the voltage, but will lag the voltage creating a lagging true power factor with a value less than 1. In the case of capacitive loads the current is in advance of the voltage, creating a leading true power factor with a value less than 1.




In this case, the AC power has three components: real power (P), reactive power (Q) and apparent power (S). The apparent power is:

 $S = U \times I$ (where S=[kVA], P=[kW] and Q=[kVAR])

In the case of a perfectly sinusoidal waveform P, Q and S can be expressed as vectors that form a triangle:

$$s^2 = P^2 + Q^2$$



The displacement angle between current and voltage is  $\varphi$ . The displacement power factor is the ratio between the active power (P) and apparent power (S):

$$DPF = \frac{P}{S} = cos(\varphi)$$


#### 3.1.2 Non-linear Loads


Non-linear loads (such as diode rectifiers) draw a nonsinusoidal current. The figure below shows the current drawn by a 6-pulse rectifier on a three phase supply.

A non-sinusoidal waveform can be decomposed in a sum of sinusoidal waveforms with periods equal to integer multiples of the fundamental waveform.

$$f(t) = \sum a_h \times \sin(h\omega_1 t)$$

See following illustrations.





The integer multiples of the fundamental frequency  $\omega 1$  are called harmonics. The RMS value of a non-sinusoidal waveform (current or voltage) is expressed as:

$$I_{RMS} = \sqrt{\frac{h_{max}}{\sum_{h=1}^{\infty} I_{(h)}^2}}$$

The amount of harmonics in a waveform gives the distortion factor, or total harmonic distortion (THD), represented by the ratio of RMS of the harmonic content to the RMS value of the fundamental quantity, expressed as a percentage of the fundamental:

$$THD = \sqrt{\frac{h_{max}}{\sum_{h=2}^{I}} \left(\frac{I_h}{I_1}\right)^2} \times 100\%$$

Using the THD, the relationship between the RMS current  $I_{RMS}$  and the fundamental current  $I_1$  can be expressed as:  $I_{RMS} = I_1 \times \sqrt{1 + THD^2}$ 

The same applies for voltage.

The true power factor PF ( $\lambda$ ) is:  $PF = \frac{P}{S}$ 

In a linear system the true power factor is equal to the displacement power factor:

$$PF = DPF = cos(\varphi)$$

In non-linear systems the relationship between true power factor and displacement power factor is:

$$PF = \frac{DPF}{\sqrt{1 + THD^2}}$$

The power factor is decreased by reactive power and harmonic loads. Low power factor results in a high RMS current that produces higher losses in the supply cables and transformers.

In the power quality context, the total demand distortion (TDD) term is often encountered. The TDD does not characterize the load, but it is a system parameter. TDD expresses the current harmonic distortion in percentage of the maximum demand current IL.

$$TDD = \sqrt{\frac{h_{max}}{\sum_{h=2}^{L} \left(\frac{I_h}{I_L}\right)^2} \times 100\%}$$

Another term often encountered in literature is the partial weighted harmonic distortion (PWHD). PWHD represents a weighted harmonic distortion that contains only the




harmonics between the 14th and the 40th, as shown in the following definition:

$$PWHD = \sqrt{\frac{40}{\sum_{h=1.4}^{2}} \left(\frac{l_h}{l_1}\right)^2} \times 100\%$$

# 3.1.3 The Effect of Harmonics in a Power Distribution System

The figure below shows an example of a small distribution system. A transformer is connected on the primary side to a point of common coupling PCC1, on the medium voltage supply. The transformer has an impedance  $Z_{xfr}$  and feeds a number of loads. The point of common coupling where all loads are connected together is PCC2. Each load is connected through cables that have an impedance  $Z_1$ ,  $Z_2$ ,  $Z_3$ .



Harmonic currents drawn by non-linear loads cause distortion of the voltage because of the voltage drop on the impedances of the distribution system. Higher impedances result in higher levels of voltage distortion.

Current distortion relates to apparatus performance and it relates to the individual load. Voltage distortion relates to system performance. It is not possible to determine the voltage distortion in the PCC knowing only the load's harmonic performance. In order to predict the distortion in the PCC the configuration of the distribution system and relevant impedances must be known.


A commonly used term for describing the impedance of a grid is the short circuit ratio  $R_{sce}$ , defined as the ratio between the short circuit apparent power of the supply at the PCC ( $S_{sc}$ ) and the rated apparent power of the load ( $S_{equ}$ ):

$$R_{sce} = \frac{s_{ce}}{s_{equ}}$$

where 
$$s_{sc} = \frac{U^2}{Z_{supply}}$$
 and  $s_{equ} = U \times I_{equ}$ 

#### The negative effect of harmonics is twofold:

- Harmonic currents contribute to system losses (in cabling, transformer)
- Harmonic voltage distortion causes disturbance to other loads and increase losses in other loads



# 3.2 Harmonic Limitation Standards and Requirements

The requirements for harmonic limitation can be:

- Application specific requirements
- Requirements from standards that have to be observed

The application specific requirements are related to a specific installation where there are technical reasons for limiting the harmonics.

For example on a 250kVA transformer with two 110kW motors connected. One is connected direct on-line and the other one is supplied through a frequency converter. If the direct on-line motor should also be supplied through a frequency converter the transformer will, in this case, be undersized. In order to retrofit, without changing the transformer, the harmonic distortion from the two drives has to be mitigated using AHF filters.

There are various harmonic mitigation standards, regulations and recommendations. Different standards apply in different geographical areas and industries. The following encountered standards will be presented:

- IEC/EN 61000-3-2
- IEC/EN 61000-3-12
- IEC/EN 61000-3-4
- IEC 61000-2-2
- IEC61000-2-4
- IEEE 519
- G5/4



# IEC 61000-3-2, Limits for harmonic current emissions (equipment input current ≤ 16A per phase)

The scope of IEC 61000-3-2 is equipment connected to the public low-voltage distribution system having an input current up to and including 16 A per phase. Four emission classes are defined: Class A through D. The VLT drives are in Class A. However, there are no limits for professional equipment with a total rated power greater than 1 kW.

# IEC 61000-3-12, Limits for harmonic currents produced by equipment connected to public low-voltage systems with input current >16A and ≤75A

The scope of IEC 61000-3-12 is equipment connected to the public low-voltage distribution system having an input current between 16A and 75A. The emission limits are currently only for 230/400V 50Hz systems and limits for other systems will be added in the future. The emission limits that apply for drives are given in Table 4 in the standard. There are requirements for individual harmonics (5th, 7th, 11th, and 13th) and for THD and PWHD. Frequency converters from the Automation Drive series (FC 102 HVAC, FC 202 Aqua and FC 302 Industry) comply with these limits without additional filtering.

# IEC 61000-3-4, Limits, Limitation of emission of harmonic currents in low-voltage power supply systems for equipment with rated current greater than 16A

IEC 61000-3-12 supersedes IEC 61000-3-4 for currents up to 75A. Therefore the scope of IEC 61000-3-4 is equipment with rated current greater than 75A connected to the public low-voltage distribution system. It has the status of *Technical report* and should not be seen as an international standard. A three-stage assessment procedure is described for the connection of equipment to the public supply and equipment above 75A is limited to stage 3 *connection based on the load's agreed power*. The supply authority may accept the connection of the equipment on the basis of the agreed active power of the load's installation and local requirements of the power supply authority apply. The manufacturer shall provide individual harmonics and the values for THD and PWHD.

# IEC 61000-2-2 and IEC 61000-2-4 Compatibility levels for low-frequency conducted disturbances

IEC 61000-2-2 and IEC 61000-2-4 are standards that stipulate compatibility levels for low-frequency conducted disturbances in public low-voltage supply systems (IEC 61000-2-2) and industrial plants (IEC 61000-2-4). These low-frequency disturbances include but are not limited to harmonics. The values prescribed in these standards shall be taken into consideration when planning installations. In some situations the harmonic compatibility levels can not be observed in installations with frequency converters and harmonic mitigation is needed.

# IEEE519, IEEE recommended practices and requirements for harmonic control in electrical power systems

IEEE519 establishes goals for the design of electrical systems that include both linear and nonlinear loads. Waveform distortion goals are established and the interface between

sources and loads is described as point of common coupling (PCC).

IEEE519 is a system standard that aims the control of the voltage distortion at the PCC to a THD of 5% and limits the maximum individual frequency voltage harmonic to 3%. The development of harmonic current limits aims the limitation of harmonic injection from individual customers so they will not cause unacceptable voltage distortion levels and the limitation of the overall harmonic distortion of the system voltage supplied by the utility.

The current distortion limits are given in Table 10.3 in the standard and depend on the ratio  $I_{SC}/I_L$  where  $I_{SC}$  is the short circuit current at the utility PCC and  $I_L$  is the maximum demand load current. The limits are given for individual harmonics up to the 35th and total demand distortion (TDD). Please note that these limits apply at the PCC to the utility. While requiring individual loads to comply with these limits also ensures the compliance at the PCC, this is rarely the most economic solution, being unnecessarily expensive. The most effective way to meet the harmonic distortion requirements is to mitigate at the individual loads and measure at the PCC.

However, if in a specific application it is required that the individual drive should comply with the IEEE519 current distortion limits, an AHF can be employed to meet these limits

#### G5/4, Engineering recommendation, planning levels for harmonic voltage distortion and the connection of nonlinear equipment to transmission systems and distribution networks in the United Kingdom

G5/4 sets planning levels for harmonic voltage distortion to be used in the process of connecting non-linear equipment. A process for establishing individual customer emission limits based on these planning levels is described. G5/4 is a system level standard.

For 400 V the voltage THD planning level is 5% at the PCC. Limits for odd and even harmonics in 400V systems are given in Table 2 in the standard. An assessment procedure for the connection of non-linear equipment is described. The procedure follows three stages, aiming to balance the level of detail required by the assessment process with the degree of risk that the connection of particular equipment will result in unacceptable voltage harmonic distortion.

Compliance of a system containing VLT® frequency converters depends on the specific topology and population of non-linear loads. AHF can be employed to meet the requirements of G5/4.



#### 3.3 Harmonic Mitigation

To mitigate the harmonics caused by the frequency converter 6-pulse recitifier several solutions exist and they all have their advantages and disadvantages. The choice of the right solution depends on several factors:

- The grid (background distortion, mains unbalance, resonance and type of supply - transformer/ generator)
- Application (load profile, number of loads and load size)
- Local/national requirements/regulations (IEEE519, IEC, G5/4, etc.)
- Total cost of ownership (initial cost, efficiency, maintenance, etc.)

IEC standards are harmonized by various countries or supranational organizations. All above mentioned IEC standards are harmonized in the European Union with the prefix "EN". For example the European EN 61000-3-2 is the same as IEC 61000-3-2. The situation is similar in Australia and New Zealand, with the prefixes AS/NZS.

Harmonic solutions can be divided into two main categories: passive and active. Where the passive solutions consist of capacitors, inductors or a combination of the two in different arrangements.

The simplest solution is to add inductors/reactors of typically 3% to 5% in front of the frequency converter. This added inductance reduces the amount of harmonic currents produced by the drive. More advanced passive solutions combine capacitors and inductors in trap arrangement specially tuned to eliminate harmonics starting from e.g. the 5<sup>th</sup> harmonic.


The active solutions determine the exact current that would cancel the harmonics present in the circuit and synthesizes and injects that current into the system. Thus the active solution can mitigate the real-time harmonic disturbances, which makes these solutions very effective at any load profile. To read more about the Danfoss active solutions Low Harmonic Drive (LHD) or Active Filters (AAF) please see MG. 34.OX.YY and MG.90.VX.YY.



#### 4 Introduction to Advanced Harmonic Filters

#### 4.1 Operation Principle

The Danfoss Advanced Harmonic Filters (AHF) consist of a main inductor  $L_0$  and a two-stage absorption circuit with the inductors  $L_1$  and  $L_2$  and the capacitors  $C_1$  and  $C_2$ . The absorption circuit is specially tuned to eliminate harmonics starting with the  $5^{th}$  harmonic and is specific for the designed supply frequency. Consequently the circuit for 50Hz has different parameters than the circuit for 60 $\alpha$ Hz.



AHFs are available in two variants for two performance levels: AHF005 with 5% THiD (total current harmonic distortion) and AHF010 with 10% THiD. The strategy behind the two levels is to offer a performance similar to 12 pulse rectifiers with the AHF010 and a performance similar to 18 pulse rectifiers with AHF005.

The filter performance in terms of THiD varies as a function of the load. At nominal load the performance of the filter should be equal or better than 10æ% THiD for AHF010 and 5æ% THiD for AHF005.


At partial load the THiD has higher values. However, the absolute value of the harmonic current is lower at partial loads, even if the THiD has a higher value. Consequently, the negative effect of the harmonics at partial loads will be lower than at full load.

#### Example:

An 18.5kW drive is installed on a 400V/50Hz grid with a 34A AHF010 (type code AHF-DA-34-400-50-20-A). Following values are measured for different load currents, using a harmonic analyzer:

I line RMS [A]	Fundamental current at 50Hz I <sup>1</sup> RMS [A]	THiD [%]	Total harmonic current Ih RMS [A] <sup>1</sup>
9.6	9.59	5.45	0.52
15.24	15.09	13.78	2.07
20.24	20.08	12.46	2.5
25.17	25	11.56	2.89
30.27	30.1	10.5	3.15
34.2	34.03	9.95	3.39

<sup>1</sup>)The total harmonic current has been calculated. The THiD vs. load plot is shown in the following figure.



It can be observed that at partial load, 15A, the THiD is approximately 14%, compared to 10% at the nominal load of 34A. On the other hand, the total harmonic current is only 2.07A at 15A line current against 3.39A harmonic current at 34A line current. Thus, THiD is only a relative indicator of the harmonic performance. The harmonic distortion of the voltage will be less at partial load than at nominal load.

Factors such as background distortion and grid unbalance can affect the performance of AHF filters. The specific figures are different from filter to filter and the graphs below show typical performance characteristics. For specific details a harmonic design tool such as MCT 31 or Harmonic Calculation Software (HCS) should be used.

Background distortion: The design of the filters aims to achieve 10% respectively 5% THiD levels with a background distortion of THvD = 2%. Practical measurements on typical grid conditions in installations with frequency converters show that often the performance of the filter is slightly better with a 2% background distortion. However, the complexity of the grid conditions and mix of specific harmonics can not allow a general rule about the performance on a distorted grid. Therefore we have chosen to present worst-case performance deterioration characteristics with the background distortion.






Illustration 4.1 AHF005




Illustration 4.2 AHF010

Performance at 10% THvD has not been plotted. However, the filters have been tested and can operate at 10% THvD but the filter performance can no longer be guaranteed.

The filter performance also deteriorates with the unbalance of the supply. Typical performance is shown in the graphs below.




Illustration 4.3 AHF005




Illustration 4.4 AHF010

#### 4.1.1 Power Factor

In no load conditions (the frequency converter is in stand-by) the frequency converter current is negligible and the main current drawn from the grid is the current through the capacitors in the harmonic filter. Therefore the power factor is close to 0, capacitive. The capacitive current is approximately 25% of the filter nominal current (depends on filter size, typical values between 20 and 25%). The power factor increases with the load. Because of the higher value of the main inductor  $L_0$  in the AHF005, the power factor is slightly higher than in the AHF010.

Following graphs show typical values for the true power factor on AHF010 and AHF005.




Illustration 4.5 AHF005




Illustration 4.6 AHF010



#### 4.1.2 Capacitor Disconnect

If the specific application requires a higher power factor at no-load and the reduction of the capacitive current in standby, a capacitor disconnect should be used. A contactor can disconnect the capacitor at loads below 20%. It is important to note that the capacitors may not be connected at full load or disconnected at no load.

It is very important to consider the capacitive current in the design of applications where the harmonic filter is supplied by a generator. The capacitive current can overexcite the generator in no-load and low-load condition. The overexcitation causes an increase of the voltage that can exceed the allowed voltage for the AHF and the frequency converter. Therefore a capacitor disconnect should always be used in generator applications and the design carefully considered.

Compared to multi-pulse rectifiers, passive harmonic filter (such as AHF) are more robust against background distortion and supply imbalance. However, the performance of passive filters is inferior to the performance of active filters when it comes to partial load performance and power factor. For details about the performance positioning of the various harmonic mitigation solutions offered by Danfoss, please consult the relevant harmonic mitigation literature.



#### 5 Selection of Advanced Harmonic Filter

This chapter will provide guidance about how to choose the right filter size and contains calculation examples, electrical data and the general specification of the filters.

#### 5.1 How to Select the Correct AHF

For optimal performance the AHF should be sized for the mains input current to the frequency converter. This is the input current drawn based on the expected load of the frequency converter and not the size of the frequency converter itself.

# 5.1.1 Calculation of the Correct Filter Size Needed

The mains input current of the frequency converter ( $I_{FC,L}$ ) can be calculated using the nominal motor current ( $I_{M,N}$ ) and the displacement factor (Cos  $\phi$ ) of the motor. Both values are normally printed on the name plate of the motor. In case the nominal motor voltage ( $U_{M,N}$ ) is unequal to the actual mains voltage ( $U_L$ ), the calculated current must be corrected with the ratio between these voltages as shown in the following

equation:
$$I_{FC.L} = 1.1 \times I_{M,N} \times cos(\rho) \times \frac{U_{M,N}}{U_L}$$

The AHF chosen must have a nominal current ( $I_{AHF,N}$ ) equal to or larger than the calculated frequency converter mains input current ( $I_{FC,L}$ ).

#### NOTE

Do not oversize the AHF. The best harmonic performance is obtained at nominal filter load. Using an oversized filter will most likely result in reduced THiD performance.

If several frequency converters are to be connected to the same filter, the AHF must be sized according to the sum of the calculated mains input currents.

#### **NOTE**

If the AHF is sized for a specific load and the motor is changed, the current must be recalculated to avoid overloading the AHF.

#### 5.1.2 Calculation Example

System mains voltage (U <sub>L</sub> ):	380V
Motor name plate power(P <sub>M</sub> ):	55kW
Motor efficiency (η <sub>M</sub> ):	0.96
FC efficiency (η <sub>FC</sub> ):	0.97
AHF effiency (η <sub>AHF</sub> )(worst case estimate):	0.98

Maximum line current (RMS):

$$\frac{P_M \times 1000}{U_L \times \eta_M \times \eta_{FC} \times \eta_{AHF} \times \sqrt{3}} = \frac{55 \times 1000}{380 \times 0.96 \times 0.97 \times 0.98 \times \sqrt{3}} = 91.57 \text{ A}$$
In this case a 96A filter must be chosen.

#### 5.1.3 Voltage Boost

The AHF's in stand-by and under low load conditions, then the capacitors are not disconnected, boost the input voltage with up to 5%. This means that the voltage at the drive terminals is up to 5% higher than the voltage at the input of the filter. This should be considered at the design of the installation. Special care should be taken in 690V applications, where the voltage tolerance of the drive is reduced to +5%, unless a capacitor disconnect is used.



### 5.2 Electrical Data

380 - 415V, 50Hz

Code number	Code number	Filter current	Typical motor	VLT power and current	current		Losses	Acoustic noise	Frame size	size
AHF005	AHF010	rating		ratings		AHF005	AHF010			
IP00	IP00	⋖	ΚW	ΚW	∢	>	>	dBA	<b>AHF005</b>	AHF010
IP20	IP20									
130B1392 130B1229	130B1262 130B1027	10	m	PK37-P4K0	1.2-9	131	93	<70	×	×
130B1393	130B1263	14	7.5	P5K5-P7K5	14.4	184	118	<70	×	×
130B1231	130B1058									
130B1394	130B1268	22	11	P11K	22	258	206	<70	X2	X
130B1232	130B1059									
130B1395	130B1270	29	15	P15K	29	298	224	<70	X2	X2
130B1233	130B1089									
130B1396	130B1273	34	18.5	P18K	34	335	233	<72	X3	X3
130B1238	130B1094									
130B1397	130B1274	40	22	P22K	40	396	242	<72	X3	X3
130B1239	130B1111									
130B1398	130B1275	55	30	P30K	25	482	274	<72	×3	X3
130B1240	130B1176									
130B1399	130B1281	99	37	P37K	99	574	352	<72	X 4	* *
130B1241	130B1180									
130B1442	130B1291	82	45	P45K	82	889	374	<72	× 4	X 4
130B1247	130B1201									
130B1443	130B1292	96	55	P55K	96	747	428	<75	X5	X5
130B1248	130B1204									
130B1444	130B1293	133	75	P75K	133	841	488	<75	X5	X5
130B1249	130B1207									
130B1445	130B1294	171	06	P90K	171	362	692	<75	9X	9X
130B1250	130B1213									
130B1446	130B1295	204	110	P110	204	1080	742	<75	9X	9X
130B1251	130B1214									
130B1447	130B1369	251	132	P132	251	1195	864	<75	X	XX
130B1258	130B1215									
130B1448	130B1370	304	160	P160	304	1288	905	<75	X X	X X
130B1259	130B1216									
130B3153	130B3151	325	Parall	Paralleling for 355kW		1406	952	<75	X8	XX
130B3152	130B3136									
130B1449	130B1389	381	200	P200	381	1510	1175	<77>	8X	X7
130B1260	130B1217									
130B1469	130B1391	480	250	P250	472	1852	1542	<77>	8X	8X
130B1261	130B1228									



Code number AHF005	Code number AHF010	Filter current	Filter current Typical motor rating	VLT power and current ratings	ld L	Losses 5 AHF010	Acoustic noise	Frame size
IP00 IP20	IP00 IP20	· «	kW	kw A	>	>	dBA	AHF005 AHF010
2 x 130B1448 2 x 130B1259	2 × 130B1370 2 × 130B1216	809	315	P315 590	00 2576	1810	<80	
2 x 130B3153 2 x 130B3152	2 x 130B3151 2 x 130B3136	650	355	P355 647	.7 2812	1904	<80	
130B1448 + 130B1449 130B1259 + 130B1260	130B1370 + 130B1389 130B1216 + 130B1217	685	400	P400 684	14 2798	3 2080	<80	
2 x 130B1449 2 x 130B1260	2 x 130B1389 2 x 130B1217	762	450	P450 779	3020	2350	<80	
130B1449 + 130B1469 130B1260 + 130B1261	130B1389 + 130B1391 130B1217 + 130B1228	861	200	P500 857	7 3362	2717	<80	
2 x 130B1469 2 x 130B1261	2 x 130B1391 2 x 130B1228	096	260	P560 964	3704	3084	<80	
3 x 130B1449 3 x 130B1260	3 x 130B1389 3 x 130B1217	1140	630	P630 1090	90 4530	3525	<80	
2 x 130B1449 + 130B1469 2 x 130B1260 + 130B1261	2 x 130B1389 + 130B1391 2 x 130B1217 + 130B1228	1240	710	P710 1227	27 4872	3892	<80	
3 x 130B1469 3 x 1301261	3 x 130B1391 3 x 130B1228	1440	800	P800 1422	22 5556	, 4626	<80	
2 × 130B1449 + 2 × 130B1469 2 × 130B1260 + 2 × 130B1261	2 x 130B1449 + 2 x 130B1469 2 x 130B1389 + 2 x 130B1391 2 x 130B1260 + 2 x 130B1261 2 x 130B1217 + 2 x 130B1228	1720	1000	P1000 1675	75 6724	5434	<80	



380 - 415V, 60Hz

Code number	Codenimber AHE010	Filter current	Typical motor	VIT power and current	current	PASSO	900	Acquistic noise	Frame size	Size
AHF005	IP00	rating		ratings		AHF005	AHF010			Ì
IP00	IP20	<b>V</b>	ΚW	ΚW	⋖	>	>	dBA	AHF005	AHF010
IP20										
130B3095	130B2874	10	m	PK37-P4K0	1.2-9	131	93	<70	×	×
13081237	13005202	7,	L	ייורם היוים	7 7	707	7	Ç	5	5
130B2858	130B2265	<u>4</u>	c./	75K5-F/K5	<u>4.</u>	48	<u>×</u>	0/>	₹	<del>-</del>
130B3097	130B2876	22	11	P11K	22	258	206	<70	X2	X2
130B2859	130B2268									
130B3098	130B2877	29	15	P15K	29	298	224	<70	X2	X2
130B2860	130B2294									
130B3099	130B3000	34	18.5	P18K	34	335	233	<72	×3	X3
130B2861	130B2297									
130B3124	130B3083	40	22	P22K	40	396	242	<72	X3	X3
130B2862	130B2303									
130B3125	130B3084	55	30	P30K	55	482	274	<72	X	×3
130B2863	130B2445									
130B3026	130B3085	99	37	P37K	99	574	352	<72	X 4	X 4
130B2864	130B2459									
130B3127	130B3086	82	45	P45K	82	889	374	<72	* *	X4
130B2865	130B2488									
130B3128	130B3087	96	55	P55K	96	747	427	<75	X5	X5
130B2866	130B2489									
130B3129	130B3088	133	75	P75K	133	841	488	<75	X5	X5
130B2867	130B2498									
130B3130	130B3089	171	06	P90K	171	962	692	<75	9X	9X
130B2868	130B2499									
130B3131	130B3090	204	110	P110	204	1080	743	<75	9X	9X
130B2869	130B2500									
130B3132	130B3091	251	132	P132	251	1194	864	<75	X	X7
130B2870	130B2700									
130B3133	130B3092	304	160	P160	304	1288	905	<75	X	×
130B2871	130B2819									
130B3157	130B3155	325	Parall	Paralleling for 355kW		1406	952	<75	8X	XX
130B3156	130B3154									
130B3134	130B3093	381	200	P200	381	1510	1175	<77>	% X	X8
130B2872	130B2855									
130B3135	130B3094	480	250	P250	472	1850	1542	<77>	8X	8X
130B2873	130B2856									



Code number AHF005	Codenumber AHF010	Filter current	Typical	VLT power and current	d current	Los	Losses	Acoustic noise	Frame size
IP00	IP00	rating	motor	ratings		AHF005	AHF010		
IP20	IP20	4	ΚW	ΚM	∢	>	≥	dBA	AHF005 AHF010
2 x 130B3133	2 x 130B3092	809	315	P315	290	2576	1810	<80	
2 x 130B2871	2 x 130B2819								
2 x 130B3157	2 x 130B3155	059	315	P355	647	2812	1904	<80	
2 x 130B3156	2 x 130B3154								
130B3133 + 130B3134	130B3092 + 130B3093	685	355	P400	684	2798	2080	<80	
130B2871 + 130B2872	130B2819 + 130B2855								
2 x 130B3134	2 x 130B3093	762	400	P450	779	3020	2350	<80	
2 x 130B2872	2 x 130B2855								
130B3134 + 130B3135	130B3093 + 130B3094	861	450	P500	857	3362	2717	<80	
130B2872 + 130B3135	130B2855 + 130B2856								
2 x 130B3135	2 x 130B3094	096	200	P560	964	3704	3084	<80	
2 x 130B2873	2 x 130B2856								
3 x 130B3134	3 x 130B3093	1140	260	P630	1090	4530	3525	<80	
3 x 130B2872	3 x 130B2855								
2 x 130B3134 + 130B3135	2 x 130B3093 + 130B3094	1240	630	P710	1227	4872	3892	<80	
2 x 130B2872 + 130B2873	2 x 130B2855 + 130B2856								
3 x 130B3135	3 x 130B3094	1440	710	P800	1422	5556	4626	<80	
3 x 130B2873	3 x 130B2856								
2 x 130B3134 + 2 x 130B3135	2 x 130B3134 + 2 x 130B3135 2 x 130B3093 + 2 x 130B3094	1722	800	PIMO	1675	6724	5434	<80	
2 x 130B2872 + 2 x 130B2873	2 x 130B2872 + 2 x 130B2873 2 x 130B2855 + 2 x 130B2856								



440 - 480V, 60Hz

Code number	Codenumber	Filter current	Typical motor	VLT power and current	d current		losses	Acoustic noise	Frame size	size
AHF005	AHF010	rating		ratings		AHF005	AHF010			
IP00	IP00	V	웊	웊	⋖	>	*	dBA	<b>AHF005</b>	AHF010
IP20	IP20									
130B1787	130B1770	10	4	PK37-P4K0	1-7.4	131	93	<70	×	×
130B1752	130B1482									
130B1788	13081771	17	10	P5K5-P7K5	9.9+13	184	188	<70	×	×
130B1753	130B1483									
130B1789	130B1772	19	15	P11K	19	258	206	<70	X2	X2
130B1754	130B1484									
130B1790	130B1773	25	20	P15K	25	298	224	<70	X2	X2
130B1755	130B1485									
130B1791	130B1774	31	25	P18K	31	335	233	<72	X3	χ
130B1756	130B1486									
130B1792	130B1775	36	30	P22K	36	396	242	<72	X3	X
130B1757	130B1487									
130B1793	130B1776	48	40	P30K	47	482	374	<72	X3	X
130B1758	130B1488									
130B1794	130B1777	09	20	P37K	59	574	352	<72	X4	X4
130B1759	130B1491									
130B1795	130B1778	73	61	P45K	73	889	374	<72	X4	X 4
130B1760	130B1492									
130B1796	130B1779	95	75	P55K	95	747	428	<75	X5	X5
130B1761	130B1793									
130B1797	130B1780	118	100	P75K	118	841	488	<75	X5	X5
130B1762	130B1494									
130B1798	130B1781	154	125	P90K	154	962	692	<75	9X	9X
130B1763	130B1495									
130B1799	130B1782	183	150	P110	183	1080	743	<75	9X	9X
130B1764	130B1496									
130B1900	130B1783	231	200	P132	231	1194	864	<75	X7	X
130B1765	130B1497									
130B2200	130B1784	291	250	P160	291	1288	905	<75	XX	X X
130B1766	130B1498									
130B2257	130B1785	355	300	P200	348	1406	952	<75	X8	8X
130B1768	130B1499									
130B3168	130B3166	380				1510	1175	<77>	X8	X7
130B3167	130B3165									
130B2259	130B1786	436	350	P250	436	1852	1542	<77>	8X	X7
130B1769	130B1751									



Code number AHF005	Code number AHF010	Filter current	Typical	VLT power and current	nd current	2	Losses	Acoustic noise	Frame size
IP00/IP20	IP00/IP20	rating	motor	ratings		AHF005	AHF010		
		⋖	kw	ΚW	⋖	>	>	dBA	<b>AHF005 AHF010</b>
130B1900 + 130B2200	130B1783 + 130B1784	522	450	P315	531	2482	1769	<80	
130B1765 + 130B1766	130B1497 + 130B1498								
2 x 130B2200	2 x 130B1784	582	200	P355	280	2576	1810	<80	
2 x 130B1766	2 x 130B1498								
130B2200 + 130B3166	130B1784 + 130B3166	671	550	P400	299	2798	2080	<80	
130B1766 + 130B3167	130B1498 + 130B3165								
2 x 130B2257	2 x 130B1785	710	009	P450	711	2812	1904	<80	
2 x 130B1768	2 x 130B1499								
2 x 130B3168	2 x 130B3166	760	650	P500	759	3020	2350	<80	
2 x 130B3167	2 x 130B3165								
2 x 130B2259	2 x 130B1786	872	750	P560	867	3704	3084	<80	
2 x 130B1769	2 x 130B1751								
3 x 130B2257	3 x 130B1785	1065	006	P630	1022	4218	2856	<80	
3 x 130B1768	3 x 130B1499								
3 x 130B3168	3 x 130B3166	1140	1000	P710	1129	4530	3525	<80	
3 x 130B3167	3 x 130B3165								
3 x 130B2259	3 x 130B1786	1308	1200	P800	1344	5556	4626	<80	
3 x 130B1769	3 x 130B1751								
2 x 130B2257 + 2 x 130B2255	$2 \times 130B2257 + 2 \times 130B2259 \ 2 \times 130B1785 + 2 \times 130B1786$	1582	1350	PIMO	1490	6516	2988	<80	
2 x 130B1768 + 2 x 130B176	2 x 130B1768 + 2 x 130B1768 2 x 130B1499 + 2 x 130B1751								



600V - 60Hz

Code	Code	Filter current rating Typical motor	Typical motor	VLT Power and Current Ratings	urrent Ratings	Losses	ies	Acoustic noise		
number	number	20Hz	·		1	AHF005	AHF010		Frame Size	size
IP00/IP20	IP00/IP20	∢	운	ΚW	<b>«</b>	>	>	dBa	AHF005	AHF010
130B5261 130B5246	130B5229 130B5212	15	10	P11K	15	298	224	<70	ž,	, x
130B5262 130B5247	130B5230 130B5213	20	16.4	P15K	19.5	335	233	<70	x3	x3
130B5263 130B5248	130B5231 130B5214	24	20	P18K	24	396	242	<70	x3	×3
130B5264 130B5249	130B5232 130B5215	29	24	P22K	29	482	274	<70	×4	**
130B5265 130B5250	130B5233 130B5216	36	33	P30K	36	574	352	<70	× 4	*
130B5266 130B5251	130B5234 130B5217	20	40	P37K	49	889	374	<70	x5	x5
130B5267 130B5252	130B5235 130B5218	28	20	P45K	28	747	428	<70	x5	x5
130B5268 130B5253	130B5236 130B5219	77	09	P55K	74	841	488	<72	9x	9x
130B5269 130B5254	130B5237 130B5220	87	75	P75K	85	962	692	<72	9x	9x
130B5270 130B5255	130B5238 130B5221	109	100	P90K	106	1080	743	<72	9x	9x
130B5271 130B5256	130B5239 130B5222	128	125	P110	124	1194	864	<72	9x	9x
130B5272 130B5257	130B5240 130B5223	155	150	P132	151	1288	905	<72	X,	X,
130B5273 130B5258	130B5241 130B5224	197	200	P160	189	1406	952	<72	, X	×7
130B5274 130B5259	130B5242 130B5225	240	250	P200	234	1510	1175	<75	8×	8×
130B5275 130B5260	130B5243 130B5226	296	300	P250	286	1852	1288	<75	8×	8×



Code	Code	Filter current rating	Typical motor	VLT Power and	VLT Power and Current Ratings	Los	Losses	Acoustic noise	
number	number	50Hz				AHF005	AHF010		Frame Size
AHF005	AHF010								AHE005 AHE010
IP00/IP20	IP00/IP20	¥	웊	Κ×	∢	>	>	dBa	
2 x 130B5273	130B5244	996	250	D21E/D2EE	996/066	7017	1547	37/	9
2 x 130B5258	130B5227	0000	000	F313/F333	000/600	7107	1342	6/>	oy Y
2 x 130B5273	130B5245	700	900	0400	100	001	200	71,	Ç
2 x 130B5258	130B5228	393	400	7400	393	7197	7691	c/>	ox X
2 x 130B5274 2 x 130B5242	2 x 130B5242	000	G G	0	707	000	0166		
2 x 130B5259 2 x 130B5225	2 x 130B5225		0000	1300	707	3020	7330		
2 x 130B5275 2 x 130B5243	2 x 130B5243	COL	009	DEGO	700	2704	2536		
2 x 130B5260 2 x 130B5226	2 x 130B5226	760	000	P360	949	3704	0/67		
3 x 130B5274 2 x 130B5244	2 x 130B5244	7.57	9	0630	213	7530	2000		
3 x 130B5259 2 x 130B5227	2 x 130B5227	767	000	1030	CIO	4330	3004		
3 x 130B5274 2 x 130B5244	2 x 130B5244	737	750	0210	711	7530	2004		
3 x 130B5259 2 x 130B5227	2 x 130B5227	757	067	2	=	4330	3004		
3 x 130B5275 3 x 130B5243	3 x 130B5243	000	050	0000	000	ננע	2064		
3 x 130B5260 3 x 139B5226	3 x 139B5226		006	roou	070	0000	2004		
4 x 130B5274 3 x 130B5244	3 x 130B5244		1050	0000	000	0409	9096		
4 x 130B5259 3 x 130B5227	3 x 130B5227	00%	0601	1900 1	076	0040	4020		
4 x 130B5275 3 x 130B5244	3 x 130B5244	1008	1160	ONTO	1037	7408	9636		
4 x 130B5260 3 x 130B5227	3 x 130B5227	060	001		1032	004/	1070		
7	4 x 130B5244	1500	1250	CAALO	7001		6160		
7	4 × 130B5227	000	000	71817	1221		8010		



500-690V-50Hz

		Ciltor curront rating		T Dating to The sound T IV	Puc.	i+co +cox	250		10000				
	-	בוונפו כמוופווני ופנוווני		, L		Typical	Š		6601	ß		Ĺ	į
			Typical			motor					Acoustic	Frame size	size
	Code number	50Hz	motor size	500-550V	200	size	551-690V	<b>^</b> 06	AHF005	AHF010	noise	1000H	AUT010
	ATITOTO ILLOOVIEZO	c	Y .	KW	<	2	2	τ.	\$	\$	Pan	2001	
130B5000 130B5088	13085297	15	7,5	P11K	15	15	P15K	16	298	224	<70	చ	×3
130B5017	130B5298												
13085089	130B5298 130B5281	20	11	P15K	19,5	18.5	P18K	20	335	233	<70	χ	x3
13085018	13085299												
130B5090	130B5282	24	15	P18K	24	22	P22K	25	396	242	<70	ద	×3
13085019	130B5302	ç	C C	7000	S	ç	7000	7	6		ţ	7	
130B5092	130B5283	67	C.81	P22R	8	30	P30K	<u>~</u>	487	7/4	0/>	* *	× 4
130B5021	130B5404	ć	ć	7000	ò	1	71.0	C	]	r L	Ļ	7	
130B5125	130B5284	30	77	P30K	8	3/	P3/K	82	5/4	352	0/>	* *	× 4
130B5022	130B5310	C	C	77.00	Ş	76	DAEK	90	003	27.4	02/	ų	,
130B5144	130B5285	90	30	F3/R	<del>4</del>	<del>.</del> 64	P45K	δ4	880	5/4	0/>	Q	ç
130B5023	130B5324	0 1	7.0	DAEK	C	U	DEEK	7.3	777	907	05/	ų	<u>ا</u>
130B5168	130B5286	000	/6	743K	96	23	LOOK	) c	/+/	470	0//	Q	Ş
130B5024	130B5325	77	7.5	DEEK	7	7.5	DZEK	76	841	887	72/	ķ	4
130B5169	130B5287		P		-	2		2	<u>-</u>	9	7//	ę	2
130B5025	130B5326	0.7	i i	DZEV	C				790	603	۲,	ý	4
130B5170	130B5288	/0	CC	F/3R	60				706	760	7/>	Q X	e X
130B5026	130B5327	00	75	7000	,	S	7000	707	000	743	, c.	ý	ý
130B5172	130B5289	, 60	۲)	7067 V	2	2	A087	5	0001	/43	7/>	<b>Q</b>	e X
130B5028	130B5328	178	C	0110	130	110	0110	176	1104	86.4	72/	ķ	ý
130B5195	130B5290	07-	S	2	2	2	2	0	<u>+</u>	† 0	7/7	R	2
130B5029	130B5329	r L	7		Ç	,			000	Ü	ĊĘ,	Ļ	Ļ
130B5196	130B5291	ccl	2	F132	000	132	F132	061	007	60%	7/>	×	×
130B5042	130B5330	107	127	0160	100	091	0310	106	1406	053	۲,	7	7
130B5197	130B5292		75	201	0	3	2	00	500	332	7/5	≷	```
130B5066	130B5331	070	091	0000	JAE	000	0000	757	1510	1175	37/	9	9
130B5198	130B5293	740	20	1200	C+7	700	0071	<b>4</b> 24	0 0	6/11	6/>	9	οχ
130B5076	130B5332	296	200	P250	299	250	P250	280	1852	1288	<75	×	×
130B5199	130B5294	0)	227	2	)	2	2	200	700	200		Ş	2



	11	Filter Current rating		WIT Power and Current Batings	and Circ	rent Rati	200		36350	یو			
			•	; ; ;	, '	10000	6			<b>?</b>			
			Typical			notor					Acoustic	Frame size	size
	Code number	50Hz	motor size	500-550V	> 0	size kw	551-690V		AHF005	AHF010	noise	AHEOOS	AHE010
2 × 130B5042	130B5333					315/35	_	:	:	:	3	200	
2 × 130B5197	13085295	366	250	P315	355	2		333/368	2812	1542	<75		8 8 8
2 x 130B5042	130B5334	,		7		000				210	71,		ç
2 x 130B5197	130B5296	395	315	F355	38	400			7187	7681	\$/>		× ×
130B5042	130B5330												
+ 130B5066	+ 130B5331	737	255	0000	413	003	0070	205	2016	7117			
130B5197	130B5292	) (†	777	5	<u>t</u>	2	5	260	0167	7717			
+ 130B5198	+ 130B5293												
130B5066	130B5331												
+ 130B5076	+ 130B5332	963	00	0450	701	0	0030	707	7367	2463			
130B5198	130B5292	000	004	7430	504	200	1300	707	2000	2403			
+ 130B5199	+ 130B5294												
2 x 130B5076	2 x 130B5332	203	750	0030	27.7	069	DEGO	0.64	7004	2575			
2 x 130B5199	2 x 130B5294	292	t 0	2005	1/0	050	000	, ,	1000	0/67			
130B5076	13085332												
+ 2x130B5042	+ 130B5333	(33	00	0220	(1)	0,1	0630	613	7007	0000			
130B5199	130B5294	700	000	P300	047	2	Posu	510	4004	7830			
+ 2 x 130B5197	+ 130B5295												
4 × 130B5042	2 x 130B5333	737	760	DK30	7.13	008	0710	711	7674	2087			
4 x 130B5197	2 x 130B5295	132		000	f	9	2	=	1000	toon			
3 x 130B5076	3 x 130B5332	000	023	0170	990	000	0000	000	נננ	7900			
3 x 130B5199	3 x 130B5294	0000	0/0	2	000	000	000	070	2220	2004			
2 × 130B5076	2 x 130B5332												
+ 2 × 130B5042	+ 130B5333	840	350	0000	7	000	0000	000	717	71			
2 x 130B5199	2 x 130B5294	930	730	7000 0000	705	3	00%	076	0100	4 - 0			
+ 2 x 130B5197	+ 130B5295												
6 x 130B5042	3 x 130B5333	1008	030	D1M0	1070		D1M0	1032	9736	9636			
6 x 130B5197	3 x 130B5295	000	200		0/0			700	0000	0704			


#### 5.2.1 Accessories

IP21/NEMA1 enclosure kits for the IP20 filters are available and listed here:

	IP21/NEMA1 kit for IP20
Danfoss part number	enclosure
130B3274	X1
130B3275	X2
130B3276	Х3
130B3277	X4
130B3278	X5
130B3279	Х6
130B3281	X7
130B3282	X8

The kit consists of two parts:

A top plate that prevents vertically falling drops of water and dirt from entering the filter and a terminal cover ensuring touch safe terminals. The terminal cover is prepared for installation of a contactor for capacitor disconnect.



Enclosure type	a	b	с	d	e
	(mm)	(mm)	(mm)	(mm)	(mm)
X1	120	160	329.5	344.5	215.5
X2	190	180	433.5	448.5	257.5
X3	145	210	543.5	558.5	252
X4	230	230	573.5	558.5	343
X5	230	250	681.5	696.5	343
X6	300	270	681.5	696.5	410
X7	300	320	796.5	811.5	458.5
X8	400	350	796.5	811.5	553



#### **NOTE**

The NEMA 1 cover is designed for the mounting of Danfoss contactors.

When using non Danfoss contactors, please observe the dimensions of the NEMA 1 terminal cover and ensure that there is space for the contactor.

#### 5.3 General Specification

#### 5.3.1 General Technical Data

Supply voltage tolerance	+/- 10%
Supply frequency tolerance	+5 %/-1.5%
Overload capability	160% for 60 seconds
Efficiency	>0.98
THiD*	AHF005 < 5%
	AHF010 < 10%
Cos φ of I <sub>L</sub>	0.5 cap at 25% I <sub>AHF,N</sub>
	0.8 cap at 50% l <sub>AHF,N</sub>
	0.85 cap at 75% I <sub>AHF,N</sub>
	0.99 cap at 100% laнғ,n
	1.00 cap at 160% I <sub>AHF,N</sub>
Power derating	Temperature - see derating
	curve below.
	1000 m altitude above sea
	level < h < 2000m = 5% per
	1000m

#### **NOTE**

The reduction of the low harmonic current emission to the rated THiD implies that the THvD of the non-influenced mains voltage is lower than 2% and the ratio of short circuit power to installed load (RSCE) is at least 66. Under these conditions the THiD of the mains current of the frequency converter is reduced to 10% or 5% (typical values at nominal load). If these conditions are not or only partially fulfilled, a significant reduction of the harmonic components can still be achieved, but the rated THiD values may not be observed.

		Dimensions in mr	n
<b>Enclosure Type</b>	A (height)	B (width)	C (depth)
X1	332	190	206
X2	436	232	248
Х3	594	378	242
X4	634	378	333
X5	747	418	333
Х6	778	418	396
X7	909	468	449
X8	911	468	549

**Table 5.1 Enclosure Dimensions** 

#### 5.3.2 Environmental Data

Surroundings	
Ambient temperature	5°C + 45°C - without derating
during full-scale	5°C + 60°C - with derating
operation	
Temperature during	-25°C + 65°C - transport
storage/transport	-25°C + 55°C - storage
Max. altitude above	1000 m (without derating)
sea level	Between 1000 m and 2000 m (with
	derating)
Max. relative humidity	Humidity class F without condensation -
	5% - 85% - Class 3K3 (non-sondensing)
	during operation
Insulation strength	Overvoltage category III according to ENG
	61800-5-1
Packaging	DIN55468 for transport packaging
	materials




Illustration 5.1 Temperature Derating Curve



#### 6 How to Install

#### 6.1 Mechanical Mounting

# 6.1.1 Safety Requirements of Mechanical Installation

#### **NOTE**

Please observe the filter weight and ensure that proper lifting equipment is used.

#### NOTE

When installing the filter use the lifting eyes on both sides to lift the filter.

#### NOTE

Do not use other parts (terminals, enclosures, etc.).

#### 6.1.2 Mounting

The filters are available in IP00 and IP20 and for both IP ratings the following guidance must be followed during installation.

- All filters must be mounted vertically with the terminals at the bottom
- Do not mount the filter close to other heating elements or heat sensitive material (such as wood)

#### IP00

• The surface temperature of the IP00 filters can exceed 70°C and a hot surface warning label is placed on the filter

#### IP20

- Top and bottom clearance is minimum 150mm
- The surface temperature of the IP20 filters does not exceed 70°C
- The filter can be side-by-side mounted with the frequency converter and there is no requirement for spacing between then.

# 6.1.3 Recommendations for Installation in Industrial Enclosures

To avoid high frequency noise coupling keep a minimum distance of 150mm (5.91 inches) to.

- mains/supply wires
- motor wires of frequency converter
- control- and signal wires (voltage range < 48V)

To obtain low impedance HF-connections, grounding, screening and other metallic connections (e.g. mounting plates, mounted units) should have a surface as large as possible to metallic ground. Use grounding and potential equalisation wires with a cross section as large as possible (min. 10mm²) or thick grounding tapes. Use copper or tinned copper screened wires only, as steel screened wires are not suitable for high frequency applications. Connect the screen with metal clamps or metal glands to the equalisation bars or PE-connections.

Inductive switching units (relay, magnetic contactor etc.) must always be equipped with varistors, RC-circuits or suppressor diodes.

#### 6.1.4 Ventilation


The filters are cooled by means of air circulation. Consequently the air needs to be able to move freely above and below the filter.

When mounting the filters in panels or other industrial enclosures it must be ensured that there is a sufficient airflow through the filter to reduce the risk of overheating the filter and the surrounding components.

If other heat sources (such as frequency converters) are installed in the same enclosure, the heat they generate also needs to be taken into account when dimensioning the cooling of the enclosure.

The filters have to be mounted on a wall in order to guide air through the gap between the wall and the filter. In installations (e.g. panels) where the filter is mounted on rails, the filter will not be sufficiently cooled because of false airflow and therefore a back plate can be ordered separately. See following illustration.





Danfoss part number	Back plate	
130B3283	X1	
130B3284	X2	
130B3285	Х3	
130B3286	X4	
130B3287	X5 and X6	
130B3288	X7 and X8	

#### IP20: Ventilation fan mounted:

380V, 60Hz 400V,			
50Hz	460V, Hz		
Current	Current	Fa	an
[A]	[A]	AHF010	AHF005
10	10	no	no
14	14	no	no
22	19	inside	outside
29	25	inside	outside
34	31	inside	inside
40	36	inside	inside
55	48	inside	inside
66	60	inside	inside
82	73	inside	inside
96	95	inside	inside
133	118	inside	inside
171	154	inside	inside
204	183	inside	outside
251	231	inside	outside
304	291	inside	outside
325	355	inside	outside
380	380	inside	outside
480	436	inside	outside



#### 380-480V-50 and 60Hz

Voltage ar	d frequency		AHF005			AHF010	
380-415V, 50 and 60Hz	440-480, 60Hz	thermal	air speeds	air volume	thermal	air speeds	air volume
	[A]	losses in W	m/s	m³/s	losses in W	m/s	m³/s
10	10	131	2	0,0118	93	2	0,0084
14	14	184	2	0,0166	118	2	0,0106
22	19	258	2	0,0232	206	2	0,0185
29	25	298	2	0,0268	224	2	0,0202
34	31	335	2	0,0302	233	2	0,0210
40	36	396	2	0,0356	242	2	0,0218
55	48	482	2	0,0434	274	2	0,0247
66	60	574	2	0,0517	352	2	0,0317
82	73	688	2	0,0619	374	2	0,0337
96	95	747	2	0,0672	428	2	0,0385
133	118	841	2	0,0757	488	2	0,0439
171	154	962	2	0,0866	692	2	0,0623
204	183	1080	2,5	0,0972	743	2,5	0,0669
251	231	1194	2,5	0,1075	864	2,5	0,0778
304	291	1288	2,5	0,1159	905	2,5	0,0815
325	355	1406	2,5	0,1265	952	2,5	0,0857
381	380	1510	2,5	0,1359	1175	2,5	0,1058
480	436	1852	2,5	0,1667	1542	2,5	0,1388

#### 600V - 60Hz

Voltage and frequency		AHF005			AHF010			
500-690V, 50Hz	600V, 60Hz	thermal	air speeds	air volume	thermal	air speeds	air volume	
[A]	]	losses in W	m/s	V(m³/s)	losses in W	m/s	V(m³/s)	
15		298	2	0,0268	224	2	0,0202	
20	)	335	2	0,0302	233	2	0,0210	
24		396	2	0,0356	242	2	0,0218	
29	1	482	2	0,0434	274	2	0,0247	
36	i	574	2	0,0517	352	2	0,0317	
50		688	2	0,0619	374	2	0,0337	
58		747	2	0,0672	428	2	0,0385	
77		841	2	0,0757	488	2	0,0439	
87		962	2	0,0866	692	2	0,0623	
109		1080	2	0,0972	743	2	0,0669	
128		1194	2	0,1075	864	2	0,0778	
155	5	1288	2,5	0,1159	905	2,5	0,0815	
197		1406	2,5	0,1265	952	2,5	0,0857	
240		1510	2,5	0,1359	1175	2,5	0,1058	
296		1852	2,5	0,1667	1288	2,5	0,1159	
366		-	-	-	1542	2,5	0,1388	
395		-	-	-	1852	2,5	0,1667	



#### 6.2 Electrical Installation

#### 6.2.1 Over Temperature Protection

The Danfoss harmonic filters AHF005 and AHF010 are all equipped with a galvanic isolated switch (PELV) that is closed under normal operating conditions and open if the filter is overheated.

#### NOTE

The over temperature protection must be used to prevent damage of the filter caused by over temperature. An immediate stop or a controlled ramp down within max. 30 sec. has to be performed to prevent filter damage. There are many ways the switch can be used and one example is to connect terminal A of the harmonic filter to terminal 12 or 13 (voltage supply digital input, 24V) of the Danfoss frequency converter and terminal B to terminal 27. Program digital input terminal 27 to *Coast Inverse*. The frequency converter will coast the motor and thereby unload the filter if an over temperature is detected. Alternatively use terminal 12/33 and set *1-90 Motor Thermal Protection*.




Illustration 6.1 Connection Diagram

#### NOTE

The maximum rating of the over temperature contactor is 250V AC and 10A.

#### 6.2.2 Capacitor Disconnect


The power factor of the harmonic filter AHF 005/010 is decreasing with decreasing load. At no load the power factor is zero and the capacitors produce leading current of approximately 25% of rated the filter current. In applications where this reactive current is not acceptable the terminals X3.1,

X3.2, X3.3 and X4.1, X4, X4.3 provide access to the capacitor bank, so it can be disconnected.

Default (on delivery) the wiring will shorten terminal X3.1 with X4.1, X3.2 with X4.2 and X3.3 with X.4.3. In the case that no capacitor disconnect is required, no changes should be made to these shorted terminals.

If a disconnection of the capacitors is required a three-phase contactor should be placed between terminals X3 and X4. It is recommended to use AC3 contactors.





#### **NOTE**

It is not allowed to use one common 3 poled contactor with several paralleled Advanced Harmonic Filters.

#### NOTE

The AHF filters in stand-by and under low load conditions, when the capacitors are not disconnected, boost the input voltage with up to 5%. That means that the voltage at the drive terminals is up to 5% higher than the voltage at the input of the filter. This should be considered at the design of the installation. Special care should be taken in 690V applications where the voltage tolerance of the drive is reduced to + 5%, unless a capacitor disconnect is used.

#### **NOTE**

Only switch the contactor at less than 20% output power. Allow minimum 25 sec. for the capacitors to discharge before re-connecting

	Current	Danfoss	
Current rating	rating	Contactors for	
380-415V, 50 and	440-480V,	AHF005 and	Alternative
60Hz	60Hz	AHF010	type AC3
			Contactor
A	Α	Туре	rating <sup>1)</sup> KVAr
10	10	CI 9	1
14	14	CI 9	2
22	19	CI 9	4
29	25	CI 9	6
34	31	CI 16	7
40	36	CI 16	7
55	48	CI 16	9
66	60	CI 61	11
82	73	CI 61	15
96	95	CI 61	17
133	118	CI 61	22
171	154	CI 61	29
204	183	CI 61	36
251	231	CI 110	44
304	291	CI 110	51
325	355	CI 110	58
380	380	CI 110	66
480	436	CI 141	88

<sup>1)</sup> min. 50% of the nominal load

NOTE



#### 6.2.3 Wiring

Supply voltage must be connected to the terminals X1.1, X1.2 and X1.3. The frequency converter supply terminals L1, L2 and L3 must be connected to the filter terminals X2.1, X2.2 and X2.3

#### Paralleling of frequency converters

If several frequency converters are to be connected to one harmonic filter, the connection method is similar to the connection described above. The supply terminals L1, L2 and L3 of the frequency converters must be connected to the filter terminals X2.1, X2.2 and X2.3.

#### Use cables complying with local regulations.

#### Paralleling of filters

If the mains input current of the frequency converter exceeds the nominal current of the largest harmonic filter, several harmonic filters can be paralleled to achieve the necessary current rating - see *Electrical Data* tabels.

Supply voltage be connected to the terminals X1.1, X1.2 and X1.3 of the filters. The frequency converter supply terminals L1, L2 and L3 must be connected to the filters terminals X2.1, X2.2 and X2.3

#### Terminals and cables

The following tabels show the terminal types, cable cross section, tightening torque, etc.

		Main t	erminals		Capacitor disconnect terminals			
Current in A	Clamp mains terminals	Cable cross- section in mm <sup>2</sup>	Cable end	Torque in Nm	Clamp capacitor disconnect terminals	Cable cross- section in mm <sup>2</sup>	Cable end	Torque in Nm
10	WDU 6	0.5-10	cable end sleeve	1.6	WDU 2.5	0.5-4	cable end sleeve	0.8
14	WDU 6	0.5-10	cable end sleeve	1.6	WDU 2.5	0.5-4	cable end sleeve	0.8
22	WDU 6	0.5-10	cable end sleeve	1.6	WDU 2.5	0.5-4	cable end sleeve	0.8
29	WDU 6	0.5-10	cable end sleeve	1.6	WDU 2.5	0.5-4	cable end sleeve	0.8
34	WDU 16	1.5-25	cable end sleeve	2.4	WDU 10	1.5-16	cable end sleeve	2.4
40	WDU 16	1.5-25	cable end sleeve	2.4	WDU 10	1.5-16	cable end sleeve	2.4
55	WDU 16	1.5-25	cable end sleeve	2.4	WDU 10	1.5-16	cable end sleeve	2.4
66	WDU 35	2.5-50	cable end sleeve	4.5	WDU 16	1.5-16	cable end sleeve	2.4
82	WDU 35	2.5-50	cable end sleeve	4.5	WDU 16	1.5-16	cable end sleeve	2.4
96	WDU 50 N	10-70	cable end sleeve	6	WDU 16	1.5-16	cable end sleeve	2.4
133	WDU 50 N	10-70	cable end sleeve	6	WDU 16	1.5-16	cable end sleeve	2.4
171	WFF 70	2.5-95	cable lug M8	12	WDU 35	2.5-50	cable end sleeve	4.5
204	WFF 70	2.5-95	cable lug M8	12	WDU 35	2.5-50	cable end sleeve	4.5
251	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20
304	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20
325	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20
380	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20
480	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20

Table 6.1 380 - 415V, 50 and 60Hz



		Mair	n terminals		Capacitor disconnect terminals			
Current in A	Clamp	Cable cross-	Cable end	Torque in	Clamp	Cable cross-	Cable end	Torque in Nm
	mains	section in		Nm	capacitor	section in		
	terminals	mm²			disconnect	mm²		
					terminals			
10	WDU 6	0.5-10	cable end sleeve	1.6	WDU 2.5	0.5-4	cable end sleeve	0.8
14	WDU 6	0.5-10	cable end sleeve	1.6	WDU 2.5	0.5-4	cable end sleeve	0.8
19	WDU 6	0.5-10	cable end sleeve	1.6	WDU 2.5	0.5-4	cable end sleeve	0.8
25	WDU 6	0.5-10	cable end sleeve	1.6	WDU 2.5	0.5-4	cable end sleeve	0.8
31	WDU 16	1.5-25	cable end sleeve	2.4	WDU 10	1.5-16	cable end sleeve	2.4
36	WDU 16	1.5-25	cable end sleeve	2.4	WDU 10	1.5-16	cable end sleeve	2.4
48	WDU 16	1.5-25	cable end sleeve	2.4	WDU 10	1.5-16	cable end sleeve	2.4
60	WDU 35	2.5-50	cable end sleeve	4.5	WDU 16	1.5-25	cable end sleeve	2.4
73	WDU 35	2.5-50	cable end sleeve	4.5	WDU 16	1.5-25	cable end sleeve	2.4
95	WDU 50 N	10-70	cable end sleeve	6	WDU 16	1.5-25	cable end sleeve	2.4
118	WDU 50 N	10-70	cable end sleeve	6	WDU 16	1.5-25	cable end sleeve	2.4
154	WFF 70	2.5-95	cable lug M8	12	WDU 35	2.5-50	cable end sleeve	4.5
183	WFF 70	2.5-95	cable lug M8	12	WDU 35	2.5-50	cable end sleeve	4.5
231	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20
291	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20
355	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20
380	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20
436	WFF 300	25-300	cable lug M16	60	WDU 95 N	16-150	cable end sleeve	20

Table 6.2 440 - 480V, 60Hz

#### 6.2.4 Fuses

In order to protect the installation against electrical and fire hazards, all filters in an installation must be short-circuit and over-current protected according to national/international regulations.

To protect both drive and filter please choose the type of fuses recommended in the VLT® Design Guide. The maximum fuse rating per filter size is listed below.


Filter o	current				
380V, 60Hz 460V, 60Hz					
400V, 50Hz		Maximum size of fuse			
[A]	[A]	[A]			
10	10	16			
14	14	35			
22	19	35			
29	25	50			
34	31	50			
40	36	63			
55	48	80			
66	60	125			
82	73	160			
96	95	250			
133	118	250			
171	154	315			
204	183	350			
251	231	400			
304	291	500			
325	355	630			
380	380	630			
480	436	800			


In applications where filters are paralleled it might be necessary to install fuses in front of each filter and in front of the drive.




## 6.3 Mechanical Dimensions

## 6.3.1 Sketches










Illustration 6.2 X1 no fan









Illustration 6.3 X2 internal fan

130BB598.10










Illustration 6.4 X2 external fan






Illustration 6.5 X3 internal fan




Illustration 6.6 X4 internal fan






Illustration 6.7 X5 internal fan




Illustration 6.8 X6 internal fan




Illustration 6.9 X6 external fan




Illustration 6.10 X7 internal fan






Illustration 6.11 X7 external fan





Illustration 6.12 X8 internal fan






420 01-985880EI

Illustration 6.13 X8 external fan



## 6.3.2 IP00 Enclosures



188 mm (7.4 ln)

163 mm (6.42 ln)

6.8 mm (0.27 ln)

12 mm (0.47 ln)

188 mm (7.4 ln)

Illustration 6.14 X1







Illustration 6.15 X2






Illustration 6.16 X3







Illustration 6.17 X4







Illustration 6.18 X5









Illustration 6.19 X6






Illustration 6.20 X7






Illustration 6.21 X8

## 6.3.3 Physical Dimension

Enclosure	Dimensions in mm					
type	A (height)	A (height) B (width) C (Depth)				
X1	245	190	205			
X2	350	230	248			
Х3	460	330	242			
X4	490	330	333			
X5	747	370	333			
X6	778	370	400			
X7	909	468	450			
X8	911	468	550			

#### 6.3.4 IP00 Dimensions

Enclosure	Dimensions in mm			
Type	A (height) B (width) C (de		C (depth)	
X1	332	188	197	
X2	435	230	214	
Х3	594	378	239	
X4	624	378	333	
X5	737	418	332	
X6	767	418	415	
X7	897	468	437	
X8	898	468	490	



# 6.3.5 Weight

	AH	F010 380	- 415V,			
	50Hz			AHF005 380 - 415V, 50Hz		
Current	fra	weight	weight			weight
rating	me	IP20	IP00	frame	weight IP20	IP00
[A]	size	[kg]	[kg]	size	[kg]	[kg]
10	X1	12	8	X1	16	12
14	X1	13	9	X1	20	16
22	X2	22	17	X2	34	29
29	X2	25	5	X2	42	37
34	Х3	36	6	Х3	50	44
40	Х3	40	7	Х3	52	45
55	Х3	42	7	Х3	75	68
66	X4	52	7	X4	82	75
82	X4	56	9	X4	96	87
96	X5	62	10	X5	104	94
133	X5	74	10	X5	130	120
171	Х6	85	74	Х6	135	124
204	Х6	105	94	Х6	168	157
251	X7	123	106	X7	197	180
304	X7	136	120	X7	220	204
325	X7	142	126	X7	228	212
381	X7	163	147	X8	260	244
480	Х8	205	186	X8	328	309

	AHF01	10 380 - 41	5V, 60Hz	AHF005 380 - 415V, 60H		
Current		weight	weight		weight weight	
rating	frame	IP20	IP00	frame	IP20	IP00
[A]	size	[kg]	[kg]	size	[kg]	[kg]
10	X1	12	8	X1	16	12
14	X1	13	9	X1	20	16
22	X2	22	17	X2	34	29
29	X2	25	20	X2	42	37
34	Х3	36	30	Х3	50	44
40	Х3	40	33	Х3	52	45
55	Х3	42	35	Х3	75	68
66	X4	52	45	X4	82	75
82	X4	56	47	X4	96	87
96	X5	62	52	X5	104	94
133	X5	74	64	X5	130	120
171	X6	85	74	X6	135	124
204	X6	105	94	X6	168	157
251	X7	123	106	X7	197	180
304	X7	136	120	X7	220	204
325	X7	142	126	X7	228	212
381	X7	163	147	X8	260	244
480	X8	205	186	X8	328	309

				AHF00	5 440 -	- 480V,
	AHF	AHF010 440 - 480V, 60Hz			60Hz	
					weig	weig
Current		weight	weight		ht	ht
rating	frame	IP20	IP00	frame	IP20	IP00
[A]	size	[kg]	[kg]	size	[kg]	[kg]
10	X1	12	8	X1	16	12
14	X1	13	9	X1	20	16
19	X2	22	17	X2	34	29
25	X2	25	20	X2	42	37
31	X3	36	30	Х3	50	44
36	X3	40	33	Х3	52	45
48	X3	42	35	Х3	75	68
60	X4	52	45	X4	82	75
73	X4	56	47	X4	96	87
95	X5	62	52	X5	104	84
118	X5	74	64	X5	130	120
154	X6	85	74	X6	135	124
183	X6	105	94	X6	168	157
231	Х7	123	106	X7	197	180
291	X7	136	120	X7	220	204
355	X7	163	126	X7	260	212
380	X7	178	147	Х8	295	244
436	X8	205	186	X8	328	309

Current				weight
rating		weight IP20		IP20
[A]	Frame size	[kg]	Frame size	[kg]
15	x3	25	х3	42
20	x3	36	x3	50
24	x3	40	x3	52
29	x4	42	x4	75
36	x4	52	x4	82
50	x5	56	x5	96
58	x5	62	x5	104
77	х6	74	х6	130
87	х6	85	х6	135
109	х6	105	х6	168
128	х6	123	х6	197
155	x7	136	x7	220
197	x7	142	x7	228
240	x8	163	x8	260
296	x8	205	x8	297
366	x8	228		
395	x8	260		



## 7 How to Programme the Frequency Converter

## 7.1.1 DC-link Compensation Disabling

The FC series include a feature which ensures that the output voltage is independent of any voltage fluctuation in the DC link, e.g. caused by fast fluctuation in the mains supply voltage. In some cases this very dynamic compensation can produce resonances in the DC link and should then be disabled. Typical cases are where AHF005/010 is used on supply grids with high short circuit ratio. Fluctuations can often be recognized by increased acoustical noise and in extreme cases by unintended tripping. To prevent resonances in the DC-link, it is recommended to disable the dynamic DC-link compensation by setting 14-51 DC Link Compensation to off.

14-51	DC Lir	nk Compensation
Option	:	Function:
[0]	Off	Disables DC Link Compensation.
[1] *	On	Enables DC Link Compensation.







## Index

Α	
Abbreviations	
Active Filters1	
Apparent Power	7
_	
B	_
Background Distortion 1	2
C	
Capacitive Current1	4
Capacitor Disconnect1	4
CE Conformity And Labelling	4
D	
Derating	/
Displacement Angle	7
Power Factor	
E	
Efficiency2	7
F	
Fundamental Frequency	8
G 55/4	_
General Warning	
-	
Generator	
Grounding	9
Н	
Harmonic	
Calculation Software 1	
Mitigation Standards	
High-voltage Warning	4
I	
i IEC/EN	
61000-3-2	
61000-3-4	
IEEE 519	
IP21/NEMA1 Enclosure Kits	6
L Leading Current	2

MCT 3112
N Nominal Motor Current
O Over Temperature Protection
P Partial Load
Point Of Common Coupling
Power Factor
Reactive Power
S Screening
T The Low-voltage Directive (73/23/EEC)  Total Current Harmonic Distortion
Demand Distortion
True Power Factor 8, 13





